

SPECIFICATIONS FOR RE-CONSTRUCTION OF 08 LAYERS OUTDOOR SYNTHETIC BASKETBALL COURT

Ser No	Items	Work Description	Size of court	Qty	Rate	Amount
(a)	Base layer – Asphalt	Layer of dense- graded hot mix Asphalt	32 x19 Sq meter	608		
(b)	8 Component Acrylic Synthetic Basketball Court flooring work	1 Layer EP 2 Primer				
		2 Layer Acrylic Resurface				
		3 Layer Rubberised Cushion 01 x Lush Anti Skid Base Coat				
		1 Layer Anti Skid base Coat				
		1 layer UV Top Coat				
		Overline markings as per the game standards (Colour combination as per school preference)				
		Linework: Heavy-bodied acrylic latex paint for court lines.				
(c)	Basketball Pole	Acrylic Basketball board with fix Pole	-	02	-	-

Terms & Conditions

- Sealed Tenders are invited from reputed Contractors / Firms in Army Public School Raiwala (**Contact No - 8449712023**).
- The price quoted should be include all taxes.
- The bidders are requested to visit the site before quoting the bid.
- The school reserves the right to cancel/ call off any quotation at any stage without assigning any reasons.
- Payment will be made only after the successful installation/ construction of the works as found satisfactory to the competent authority.
- Warranty period will be one years, for any wear and tear. Contractor will provide its services without any charge.
- Completion of work shall be 45 days from the date of receipt of order.
- Corrigendum/ addendum, if any, will be posted on school website well in time **website www.apsraiwala.com**



D 25/6/2023

Principal
Army Public School
Raiwala Mil Stn